

# Galactic/Extragalactic ULDB Spectroscopic-Stratospheric Terahertz Observatory (GUSTO)

### **Project Update**

Principle Investigator

Deputy PI

Project Manager

**Deputy Project Manager** 

**Payload Manager** 

**Deputy Payload Manager** 

Dr. Christopher Walker


Dr. Craig Kulesa

Matthew Reinhart

Richard Fitzgerald

Hop Bailey

David Dolana













## GUSTO Observational Objectives: [CII], [OI], & [NII] Surveys of MW and LMC



Herschel CII line of sight (LOS): GUSTO will observe 540,000 LOS's



25 sq. degree LMC Survey




## Spectral Resolution is Key to Disentangling Complex Lines of Sight






## Stratospheric Terahertz Observatory (STO): Pathfinder for GUSTO



STO provides GUSTO experience:

- Teaming arrangements
- Gondola and instrument architecture
- Observing profile and mission plan
- Data product management







### STO-2 Mission Operations Center: McMurdo, Antarctica





## Mission Overview

#### NASA's First Balloon Class D Explorer Mission

- Designated as a Category 3, Class D Mission
- First Balloon Explorer Mission of Opportunity selected for Phases B-F.

#### Project Management

- UA: PI, Payload
- APL: PjM, MSE, Gondola, MOPS
- NASA BPO: Balloon hardware, launch services

#### Mission Profile


- First full balloon science mission that will:
  - Use the NASA developed Super Pressure Balloon system
  - Fly for 75 days or more at 110 kft (33.5 km) altitude
- Launch from Antarctica in December 2021
- Mapping mission:
  - Slow scans across Milky Way and Large Magellanic Cloud
- ~100% duty cycle science observations

#### • Science Payload:

- 0.9-m F/10 Cassegrain telescope optimized for THz frequencies
- 3x8 pixel array of cryogenically cooled heterodyne detectors
- 150 liter LHe cryostat maintains detectors at 4K for 100+ days

#### Gondola (Observing Platform):

- 2.5 axis stabilized gravity gradient attitude control system
- Power system with solar arrays and Li-lon rechargeable batteries
- Liquid cooling system to support payload heat dissipation requirements
- Telecomm & balloon control via NASA provided SIP electronics





GUSTO Gondola Stats					
Dimensions (W x D x H)	24.5 x 15.5 x 21.5 ft				
Observatory CBE mass	1459 kg				
Average power usage	1000 W				
Average power generation	1700 W				

GUSTO is the pathfinder for future bold balloon programs




### **Project Timeline**







## **GUSTO** Cryostat in flight lab at UofA





## **Band 3 HEB Array Assembly at SRON**







## Crystal Ball: Risk Management

	5- Very High					
Likelih	4- High	GUSTO-R-073 GUSTO-R-074	GUSTO-R-028			
Likelihood of Occurrence	3- Moderate			GUSTO-R-008		
Occu	2- Low			GUSTO-R-045 GUSTO-R-070	GUSTO-R-010 GUSTO-R-025	
rrence	1- Very Low				GUSTO-R-006 GUSTO-R-066	
		1 - Very Low	2 - Low	3 - Moderate	4 - High	5 - Very High

**Consequence of Occurrence** 

Top Ten	Code	Motion	Title	Approach
1	800	t	Band 3 QCL LO meeting all requirements on schedule	Mitigate
2	028	t	Super Pressure Balloon Lifetime	Watch
3	010	=	Band 3 Receiver Performance	Watch
4	025	=	IF standing waves in spectra	Mitigate
5	070	=	Gondola CG positioning	Mitigate
6	045	+	Late Start of I&T in Antarctica Causing 1 Year Launch Delay	Watch
7	073	=	Cost Growth in APL Estimate	Mitigate
131			0.00	ACC N





### Total Mission Budget vs. Baseline





### **GUSTO** is a Team Effort



## Knowledge Leadership Passion Grit

### **Science Team**

- Sets Science Objectives & Requirements
- Keeps "eyes on the prize"

### **Explorer Program Office**

- Your extended project Family
- Advocates within the NASA system
- Deep knowledge of how to run a mission
- Access to unique resources
- Always ready to help

### SMA

- Helps keep bad things from happening
- When they do, provides a path forward

### **Project Management**

- Keeps project on schedule and cost
- Risk Management

### **Instrument Team**

- Turns ppts into reality
- Works to achieve the requirements necessary for mission success



## Light at End of the Tunnel



Phase E/F